

**ENGINEERING ANALYSIS**  
**CITY OF HARTSELLE AIR CURTAIN INCINERATOR**  
**FACILITY NO. 712-0107-X001**

On September 24, 2020, local approval and applications for an Air Permit were received from the City of Hartselle, for installation of an Air Curtain Incinerator (ACI) located at 1321 Industrial Drive SE. A fee of \$7,185.00 has been assessed. A Greenfield site inspection was conducted on October 19, 2020, and no problem areas were noted. A 15 day public comment period will begin on November 30, 2020.

This facility will be subject to 40 CFR Part 60 Subpart EEEE – Standards of Performance for Other Waste Incineration Units. This facility which incinerates 100% wood waste, 100% clean lumber, or 100% mixture of wood waste, clean lumber, and/or yard waste will be required to meet the New Source Performance Standards (NSPS) visible emission limit of 10% opacity and an opacity limitation of 35% during the start-up period that is within the first 30 minutes of operation. In order to determine initial compliance with the NSPS for new facilities, a Method 9 visible emission observation will be required within 180 days of startup. After the initial test for opacity, an annual test must be conducted no more than 12 months following the date of the previous test.

This facility may operate five days per week. See proviso (s) seven (7) and eight (8) regarding the hours of operation.

The ACI will be 19'8" long, 7'1" deep and 6'2" wide. The ACI will be equipped with overfire and underfire air blowers, and will have refractory panel walls. The unit conforms to the specifications required by the Department.

This site is located approximately 744 feet from The Morgan County Environmental Services Department. Emissions from this source should not significantly affect this area.

I recommend that Air Permit No. 712-0107-X001 for the Air Curtain Incinerator be issued with the attached provisos.

---

Catrice Alexander  
Energy Branch  
Air Division

DRAFT